

GREATER HYDERABAD MUNICIPAL CORPORATION

Office of the Executive Engineer,
(Project Division- West Zone - I),
Greater Hyderabad Municipal Corporation,
6th Floor, Tank Bund,
Hyderabad.

Lr.No.EE/PD WZ-I/GHMC/2022-23/ 199

Date: 24-01-2023


To
The Commissioner,
Information & Public Relations Department,
Govt. of Telangana, Samachar Bhavan,
A.C.Guards, Hyderabad-500028.

Sir,

Sub:- Publication of Quotation Notice in Newspapers – Three different languages – Reg.

Ref:- Quotation Notice No.02/EE/PD WZ-I/GHMC/2022-23, Date:24.01.2023.

With reference to the subject cited, it is requested to arrange for the publication of Notice inviting Sealed Quotations for **“Supply, delivery, installation, testing & commissioning of Submersible pumps of capacity 2 lakh litre per hour @15m head, control panel for auto operation of pumps, supply of 62.5 KVA DG set with ATS panel with both auto and manual operation compatible”** in Three different languages i.e. Telugu, English, Urdu daily News papers immediately.



Yours faithfully,

(24/1/23)
Executive Engineer,
PD WZ-I, GHMC.

Encl:- Copy of Notification

Published in 3 papers on 25.1.2023
1) Namaste the Telangana
2) Times of India
3) Siasat

24/1/23

Supply, delivery, installation, testing & commissioning of Submersible pumps of capacity 2 lakh litre per hour @15m head, control panel for auto operation of pumps, 62.5 KVA DG set with ATS panel with both auto and manual operation compatible.

S.No.	Description of Specifications	Unit	Qty
1	Supply, delivery, installation, testing & commissioning of Submersible pumps of capacity 2 lakh liter per hour @15m head, CI body CI impeller 13.5KW/415V/50Hz, complete with delivery side elbows and accessories as required.	Nos	2
2	Supply, delivery and installation, testing & commissioning of Outdoor Wall/ stand Mount non-compartmentalized Control panel of auto operation of pumps with float switches with 20m cable for each pump and lifting chain pulley for pumps. Panel shall comply with latest revision of the standards issued by IS/ IEC Control Panel shall be suitable for 415V, 3 phase, 4 wire, 50 Hz power supply, the panel shall confirm to IP-54. Circuit breakers /contactors for motor feeders shall be selected as per IS/ IEC from selected manufacturers. Including FAT Test reports a. Incoming: Single Incomer MCCB Breaker , b. Outgoing: 2 No's Stardelta Starter Pumps outgoing feeders c. Potential free contacts for auto on/off of the pumps d. Cable: Al conductor XLPE Insulation cable (each pump @20Mtrs) including Cable glands, Lugs	Nos	1
3	Supply, delivery and installation, testing & commissioning of 62.5KVA , 0.8 PF (Kirloskar make), 415V, 3 phase, 4W,50Hz, solidly grounded DG complete with Alternator, Battery, Exhaust pipe, Micro Processor Based control panel silencer and weather proof Acoustic enclosure and all necessary interconnecting pipe work and valves. Including FAT Test reports DG shall comply with latest revision of the standards issued by IS/ IEC. Including Cable, Cable glands, Lugs and Cable tray between DG, ATS and Control Panel	Set	1
4	Supply, delivery and installation, testing & commissioning of ATS panel with both auto and manual operation compatible, auto start whenever EB power fails and demand for pump to start, Circuit Breaker and ATS Panel shall comply with latest revision of the standards issued by IS/ IEC	Set	1
5	Supply, delivery and installation of IP65 panel for ATS	No	1
6	Supply, delivery and installation of Isolator panel @EB incoming, IP65 with 100A MCCB	No	1
7	Supply, delivery and installation of CU plate electrode earth pit for DG Neutral earthing	No	1
8	Supply, delivery and installation of suitable GI pipe electrode with earth pit for DG & panels body earthing including suitable size of earthing Strip and Earthing cables, lugs.	Set	1

9	250mm DIA GI Pipe (20M For Each Pump), Complete with supports as required, One Coat of Primer and Two Coasts of Enamel Paints, Laid in Ground / Above Ground ETC..	RMT	40
---	--	-----	----

[Handwritten Signature]
24/1/23

Executive Engineer,
PD-WZ-I, GHMC.

[Handwritten Signature]
24.1.23
24/1/23