

**GREATER HYDERABAD MUNICIPAL CORPORATION (GHMC)**



**Invitation for Sealed quotations for “certain item of work for construction of modern public toilet  
in Charminar Zone**

**Notice NIT.No.63/EE-09/CRZ/GHMC/2022-2023**

**Dt.09.01.2023**

**09<sup>th</sup> Jan 2023**

O/o. EXECUTIVE ENGINEER-09,  
CHARMINAR ZONE

Phone No: 8008102048

**Website: [www.ghmc.gov.in](http://www.ghmc.gov.in)**

## SCHEDULE OF BID PROCESS

Vendors are invited to submit their quotations on or before the time, date and at the office for submission as indicated below. The Bids submitted after this time and date or at any other office other than indicated herein below will not be considered under any circumstances; unless notified by the Authority with full information of the altered time, date and the office for submission. Bid document shall be downloaded from "<https://www.ghmc.gov.in>" under tenders notifications section.

**NIT.No.63/EE-09/CRZ/GHMC/2022-2023**

**dt.09.01.2023**

<b>S No.</b>	<b>Event Description</b>	<b>Particulars</b>
1	Document downloadable from website (Date & Time)	09.01.2023 from 3.00 PM onwards
2	Pre – Bid Meeting at O/o. Executive engineer-09, Charminar Zone, GHMC	11.01.2023 @ 1.00 PM
3	Quotation due date / Bid Submission date	13.01.2023 upto 3.00 PM
4	Address for communication & submission of quotations	The Executive Engineer-09, Charminar Zone, Greater Hyderabad Municipal Corporation, Moghalpura Sports Complex. Hyderabad.
5	Date & Time for opening of Technical Bid (Eligibility & Qualification Criteria)	13.01.2023 from 03.00 PM
6	Date & Time of opening of Financial Bid	13.01.2023 from 3.00 PM (Based on Technical Bids received, Date of financial bid opening might change and will be intimated accordingly)

# GREATER HYDERABAD MUNICIPAL CORPORATION

O/o. Executive Engineer-09,  
CharminarZone, GHMC.

**Nit no: 63/ EE-09/CRZ/GHMC/2022-23, Dt: 09.01.2023**

**Dear Vendors,**

GHMC desires to obtain Quotations for arriving estimate rates to float online tender towards " **construction of modern public toilet in Charminar Zone Hyderabad**".

Interested vendors are requested to **submit your Quotations through SealedCover** to O/o Executive Engineer-09,Charminar Zone, GHMC,Moghalpura sport complex, Hyderabad or through email: [eec9.ghmc@gmail.com](mailto:eec9.ghmc@gmail.com) for eligible categories for the below item listed.

## **Eligibility Criteria:**

- I. Vendors with Firm/civil registration or GST registration and PAN card, only are eligible to submit the below quotes.
- II. The vendors are required to quote their lowest rates all exclusive of any taxes in Rupees along with complete specifications,.
- III. The submitted quotes will be inspected by the technical team of GHMC whether thequotes are found strictly in conformity with the approved specifications.
- IV. Last date for submission of quotations is 13.01.2023 @ 3:00 PM.

## QUOTATION

[on the letter head of the Bidding firm]

NIT.No. 63 /EE-09/CRZ/GHMC/2022-2023 dt. 09.01.2023

**Date:**

**The Executive Engineer-09,  
Charminar Zone, GHMC,  
Moghalpura Sportcomplex  
Hyderabad.**

**Sub :-** “Invitation for Sealed quotations for “certain item of work for construction of modern public toilet in Charminar Zone,GHMC”.

Sir,

As a part of the Bid for the subject work, we here by submit the following as Bid price as our quote to the Greater Hyderabad Municipal Corporation Our financial quote is:

<i>SR. NO.</i>	<i>PARTICULARS</i>	<i>UNIT</i>	<i>QUAN TITY</i>	<i>Rate exclusive of taxes in Rs</i>	<i>AMOUNT</i>
1	Wall Mounted - LED Outdoor Light -48 W	Nos.	3		
2	Wall Grazer - LED 18W of 0.5 m length	Nos.	3		
3	Wall Grazer - LED 36W of 1m length	Nos.			
4	Foot Lighter - LED -4w	Nos.	2		
5	LED Strip -5w /m , considered 5 m of 1 no.	m	22		
6	Installation of above wires in conduits and Laying of conduits		120		
7	16 Module Box.	Nos	2		
8	6A 1 Module switch	Nos	7		
9	6A 3 pin multi socket with safety shutter.	Nos	7		
10	6/16A 3 pin multi socket with safety shutter.	Nos	6		
11	Blank Plate	Nos	2		
12	LAN connector	Nos	1		
13	Supplying, Installation, Testing & Commissioning of Earthing station with 600 mm x 600 mm x 6 mmmgalvanised iron plate & 50 mm dia. G.I. pipe, 3000mm long GI pipe (Class B or better) earth pit as per IS 3043.The earth pit shall be provided with watering pipe (ClassB) with wire messed funnel, 25x3 GI strip/ / 2X8SWG.G.I. wire up to chamber (wire or strip size as per faultlevel), disconnecting links with 600 x 600 mm (clear)RCC chamber & heavy duty 3mm thick CI chequered plate cover with hinge & stainless steel bolts. Bentonite/Charcol & Salt shall be provided for earth pits.Excavation, back filling, removal of excess soil is included in the scope	Nos.	2		

14	Bare G.I. Conductor size 8 SWG	Rmt	50		
15	Supply, Installation, Testing and Commissioning of IP IR Dome Camera. 720P @ 60fps. 2.8-10mm vari-focal. IR beam distance 30m. H.264 High Profile. TDN. PoE, 24VAC/12VDC.	Nos.	2		
16	SITC OF FIX IR BULLET 1.3 Megapixel HD IR Bullet Camera 1/3" Progressive CMOS, ICR, 0lux with IR, 1280X960: 25fps(P)/30fps(N), 2.8mm- 12mm verifocal lens, IP66, H.264/MJPEG, dual-stream, IP66, DC12V & PoE, DWDR, 3D DNR, BLC, IR: up to 30m, On-board card slot (up to 64GB) UL LISTED. CERTIFICATE CE & FCC with all mounting accessories, connectors etc.,-	Nos.	4		
17	SITC Third-party network cameras supported, Up to 6 Megapixels resolution recording, HDMI and VGA output at up to 1920x1080P resolution, with provisions to Extend number of Cameras up to 32 camera ,8/16 ch network cameras can be connected with 40M/80M/160M incoming bandwidth, Up to 2 SATA interfaces, Plug & Play with up to 16 independent PoE network interfaces, Support network detection, including network delay, packet loss, etc	Nos.	1		
18	SITC of Workstation Window 7, 64 bit, core i5 processor, Ram 4 GB, DVD- RW, 1 gbps NIC port, with keyboard , mouse and 21.5 inch LCD	Nos.	RO		
19	SITC of 4TB Enterprise Level SATA-II Hard disk for Recording Storage.	Nos.	1		
20	SITC Managed 8-port Gigabit PoE Smart Managed Switch with 2 Gigabit SFP Ports, PoE budget:130W, IEEE802.3at PoE+ Supported for CCTV Switch	Nos.	1		
21	SITC Internate 150 Mbps 4G Router	Nos.	1		
22	Supply, Installation,testing and commissioning of 20 mm dia C.P Brass angle valve with C.P copper connecting pipe, 450 mm long and nuts & washer with C.P. Brass flange complete including cutting and making good the Walls / Floors wherever required.	Each	3		
23	Supply, Installation,testing and commissioning Basin Spout:Flora Exp Part Wall Mounted Basin Mix Flora Stainless Steel Finish 'or' ChromePlating Spindle Size: 20 mm Hindware Catalogue No. F280035CP		3		
24	Providing and fixing 15 mm dia C.P. Classik Ft Bib Cock 2 In 1 with wall flange including cutting and making good the walls wherever required.Stainless Steel Finish 'or' ChromePlating Hindware Catalogue No.F200004FT				
25	Long body	Each	7		
26	Supply, Installation,testing and commissioning of C.P brass abluion health faucet assembly with 1.0 m long braided PVC hose with mounting bracket fixed on wall complete.Stainless Steel Finish 'or' ChromePlating Hindware Catalogue No. F160013CP	Each	7		

27	Providing and fixing 1.Flush Valve : Addons - Concealed Flush Valve With Control Cock Operation Concealed type with control cock operation Plate Size: 32 mm etc. Stainless Steel Finish 'or' ChromePlating Hindware :Catalogue No. F850083	Each	10		
28	Providing and fixing Urinal Flush Valve: Auto Closing Concealed Urinal Flush Valve Stainless Steel Finish 'or' ChromePlating Flange Dia: 100 mm Jaquar Product Code: PRS-CHR-073 Range: PRESSMATIC TAPS		1		
29	40 mm CP brass domical waste	Each	1		
30	caste brass bottle trap	Each	1		
31	Supply, Installation,testing and commissioning of approved make Euronics ES05 Manual Soap Dispenser with suitable for operation with less than 5 pounds of force complete with spout, shank, and fluid bottle complete in all respects including cutting and making good the walls required.	Each	1		
32	Supply, Installation,testing and commissioning of grab bar fabricated from 32 mm dia seamless stainless steel tube in washroom facilities for physically handicapped, with non-slip gripping surface complete including cutting and making good the walls and floors where required.	Each	1		
33	Supply, Installation,testing and commissioning of portable sanitary napkin machine.	Each	1		
34	Supply and providing dust bins	Each	3		
35	Supply, Installation,testing and commissioning of Fragrance Dispenser ,Euronics EA33 Perfume Dispenser	Each	2		
36	Supply, Installation,testing and commissioning of Euronics EH27 Stainless Steel Hand Dryer	Each	1		
37	Supply and providing White Foot Pedal Feminine Hygiene Bins	Each	2		
38	Supply and providing Euronics EP23 Paper Towel Dispenser (Plastic)	Each	3		
39	Supply and providing Wall Mounted Toilet Paper Holder Euronics EPH 04F Toilet Paper Holder (With Flap)	Each	7		
40	Supply and providing Soap Dispenser ,Euronics ES07L Undercounter Soap Dispenser	Each	2		
41	Supply, Installation,testing and commissioning Baby Diaper Changing Station	Each	1		
42	Providing, fixing and testing heavy quality gun metal or brass ball valve with screwed ends 20kgm class on GI or copper				

	pipe (Leader/ZOLOTO make) 40 mm (1 1/2") dia.	lines			
43	40 mm dia. nominal bore	Each	2		
44	Providing and fixing of Polyethylene water storage tank(over head) with cover and suitable locking arrangement. Capacity -1500 Ltr -Sintex or equivalent	Nos	2		
45	Capacity -1000 Ltr -Sintex or equivalent		1		
46	Capacity -200 Ltr -Sintex or equivalent		1		
47	Supply, Installation,testing and commissioning Water Purifier	Each	1		
48	Providing and Fixing Merino HPL compact laminate 750mm x 2100mm, including all necessary hardware.	Nos.	6		
49	Providing and Fixing Merino HPL compact laminated made PD Doors size : 970mm x 2100mm, including all necessary hardware.	Nos.	1		
50	Providing and Fixing Merino HPL compact laminate 970mm x 2000mm, including all necessary hardware.	Nos.	1		
51	Signage of individual Built up White Acrylic letters with thickness 18mm, fixed with plastic locators/Industrial Adhesives 102" X 12"	A1	1		
52	Signage of individual Built up White Acrylic letters with thickness 12mm, fixed with plastic locators/Industrial Adhesives 111" X 8"	A2	1		
53	Signage of individual Built up White Acrylic letters with thickness 12mm, fixed with plastic locators/Industrial Adhesives 46" X 6"	A3,A1 1	2		
54	Female box made of 304 grade 1.2mm thick Stainless Steel Sheet with laser cut and 1.2mm X 60mm raising walling and male letter will be 5mm thick imported sheet with laser cutting and the text will be black vinyl with plotter cut letters and logo. ADS make LED's and power suppliers and fixing with nut and bolts 48" X 59"	A4	1		
55	Signage of 12mm thick imported acrylic laser cut the outline of the logo and Municipal logo printed on avery Vinyl with HP latex printing with lamination 29.5" X 15"	A5	1		
56	Signage of (White acrylic logo of 18mm thickness fixed with plastic locators/Industrial Adhesives 19.6" X 12"	A6	1		
57	5mm thick imported acrylic with laser cutting and black plotter cut vinyl pasted on the acrylic surface fixing with plastic locators/ Industrial adhesives 5"X8"	A7,A8, A9,A1 0	4		
58	Interior Signages 5mm White Acrylic Background with 5mm Acrylic Laser Cut Emblems of B1 B2 B3 9" Dia		3		
59	Interior Signages 3mm White Acrylic Background with 5mm Acrylic Laser Cut Emblems of C1 C2 C3		10		

	C4 C5 C6 4" Dia				
60	Providing and filling <b>brick bat coba (40-60 mm)</b> with ce 1:3:6 (1 cement : 3 sand : 6 block bats) including mixing of % by weight of cement. Care shall be taken prior to fillir sunk portion are pressure tested by maintaining pressure fo pipes passing through walls, slabs are well grouted and se: ponding water for 100mm thickness and maintaining for 72	Cum			
61	Providing and fixing machine cut, polished 25mm thick Tandoor stone cladding with cement mortar 1:3 (1 cement : 3 coarse sand) laid and jointed with white cement slurry @ 3.3 kg/sqm including pointing with white cement slurry admixed with pigment of matching shade, including rubbing, curing, polishing etc. all complete as per Architectural drawings, and as directed by the PM. (To be secured to the backing and the sides by means of cramps and pins).	Sqm	7		
62	Providing & fixing machine cut, machine polished 20mm thick Tandoor stone cladding in size and pattern as per detail drawing or as directed by the PM. Stone fixed with required stainless steel pins / crams / dowels including drilling holes, making notches etc. for securedly fixing with crams / pins to wall. Stone fixed approved adhesive (Bal or Laticrete or equivalent approved) to plastered walls. Joints well cleaned, grouted with matching colour approved quality ready-made grout and cured including cleaning, polishing, required double legged independent scaffolding etc. all complete at all heights and leads to satisfaction of the PM.	Sqm	38		
63	Providing and fixing Urinal partitions made out of 20mm thick approved Marble stone, partitions to be machine cut and machine polished (both sides) in one piece and edges polished and semi rounded of size 600mm x 1150mm size (exposed size). Stone shall be fixed in wall securely and grouted and finished in cement sand mortar 1:3 (1 cement : 3 sand) fixed to correct line and level including chasing in wall, curing, cleaning, exposed edge of stone rounded / chamfered and polished etc. all complete as shown in the drawing and to the satisfaction of the PM. (Location : Gents toilet)	Sqm	1		
64	Providing and fixing of 20-25mm thick machine cut, machine polished Marble stone of approved quality counter top fixed and bedded over 40mm thick Kadappa stone and about 100mm wide mirror polished marble fascia all as detailed in drawing. Stones for fascia fixed with epoxy adhesive; exposed faces / edges, rounded / chamfered, mirror polished etc. complete to the approval of the PM. All junctions shall be sealed with silicon sealant. Further to include required MS framing, drilling, cutting of holes, SS pins, anchors, clamps, finishing junctions with plaster etc. complete to the entire satisfaction of the PM.				



65	600mm wide Marble Wash basin Counter (Location : Toilets)	Sqm	1		
66	450mm wide Marble counter top for drinking area with kadapa stone	Sqm	1		
67	Flooring with Polished slate stone (indian Autumn) 20mm thick slabs set over base coat of cement mortar (1:8) for 20mm thick over CC bed, including neat cement slurry of honey like consistency spread @ 3.3.kgs per sqm & jointed neatly with cement paste mixed with pigment of matching shade to full depth, including cost of all materials like cement, sand water and stone etc., complete, including seigniorage charges, labour charges for dressing of stone etc., complete for finished item of work	Sqm	1		
68	Providing & fixing required framework Glass skylight made out of 12mm thick Toughned glass fixed with necessary SS 316 grade table glass stud, hardware, Rubber gasket, loading, unloading, cartage etc as specified by the Architect. All glass to glass joint shall be 8mm wide and filled with grey silicon sealant. Prior to start of work contractor shall submit detailed full scale shop drawings including plan, elevation and detail of fixing with structure for approval of the PM. Samples of each item on full scale or smaller scale as directed by the PM shall be submitted for approval. Work shall proceed only on approval of shop drawing.	Sqm	1		

We undertake to acknowledge that the bid evaluation be carried by the Committee authorized by the Authority and the decision of the Committee will be final and binding on us, financial bids of only those Applicants who are qualified in technical evaluation to be opened.

*Applicant Signature*