

# GREATER HYDERABAD MUNICIPAL CORPORATION

## Invitation of Sealed quotations for repairs works of 2BHK Housing Colonies

The 2BHK Housing colonies were inaugurated and houses allotted to the beneficiaries, however due to delay in allotment of the completed houses, some items are damaged. Therefore it is essential to take up the replacement for the damaged items like internal wiring, internal water supply and sanitary fixtures, repairs to pump sets etc., to make these houses habitable.

The required items are not covered in Department SSR. Hence the sealed quotations are invited for the following items for 2BHK Housing colonies of GHMC located at Quthbullapur, Serilingampally and Patancheruvu Constituency area.

Sl. No	Description of the item	Unit	Qty	Rate
	<b>Electrical Items</b>			
1	Supply and Fixing of (4 sqmm mains terminal blocks) PVC Connectors including labour charges etc., complete.	No	1	
2	Supply and Fixing of (4 sqmm) pin type copper Lugs including labour charges etc., complete.	No	1	
3	Supply and fixing of flexible pipe of 25mm dia including all labour charges etc., complete. (Make : Maruthi )	Rmt	1	
4	Supply and Fixing of MS Powder coated boxes of 1.20mm thick for placing of PVC terminal box for connecting incoming and outgoing run of mains with front door openable (hinged) including GI mounting channel of suitable length for PVC connections including all labour charges etc., complete. For the following Sizes			
	a) Size : 1.45mts x 0.18mts x 0.30mts	No	1	
	b) Size : 1.20 mts x 0.15mts x 0.30 mts	No	1	
	c) Size : 1.00mts x 0.20mts x 0.20mts	No	1	
	d) Size : 0.3mts x 0.20mts x 0.20mts	No	1	
5	Supply and fixing of 63A Copper bus bar in panel board	No	1	
	<b>Water Supply, Sanitary &amp; Pumpset Repairs</b>			
6	Supply & Fixing 65mm dia CPVC Union of approved type including cost and conveyance of all materials & labour charges (Make: Ashirvad/supreme )	No	1	
7	Supply & Fixing of CPVC Taps(Bib taps) Including	No	1	

	Labour charges etc.(Make: Water Tec,)			
8	Removing, servicing and reconditioning of open well submersible 5HP/7.5HP& 10HP motors for RCC sump.	Job	1	
9	Removing, servicing and reconditioning of (6" dia) Bore well Submersible motors 5HP motors - Borewell	Job	1	
10	Labour charges for fitting of sump starter boxes in panel boards	Job	1	
11	Sump dewatering and cleaning with chlorine liquid/ powder of 100KL / 150KL &250KL.	Job	1	
12	Cleaning of Manholes and removing of silt, garbage etc.,	Job	1	
13	Cleaning of existing SWG Pipe lines of any dia.	Rmt	1	
14	Testing of Motors 5HP open well submersible in sump and dewatering of 100KL/150KL sump.	Job	1	
	<b>Other Items</b>			
15	Providing Flat numbers in parking area, Flat numbers, sump & Bore well lettering and numbering with Enamel paint, 1st quality height should be 6" and up to 12 Alphabets English letters, including cost and conveyance of all materials & Labour charges etc. Complete for finished item of works.	Job	1	
16	Supply & Fixing of Locks with Key 65mm, 6 levers Including C/C and Labour charges etc. (Make: Godrej) for Electrical Panel room	No	1	
17	Providing Block Numbers with emulsion paint with "GHMC, PMAY & HOUSING LOGO, including cost and conveyance of all materials & Labour charges etc. Complete for finished item of works.	Job	1	

\* **Note:** GST will be paid extra @ 18% separately for all the above items under "Works contract"

**Date:**

**Signature of firm**

**Note:** Therefore sealed quotations are invited for the above items in sealed cover to be submitted / sent to the following address on or before 05 -03-2024 up to 3:00 PM

**Address:** O/o Executive Engineer-III (Housing), GHMC  
2<sup>nd</sup> Floor, GHMC Office Complex,  
Opp. Hari Hara Kala Bhavan,  
Patny Center Sec- bad-500003,  
Cell No. 7995085328.

*[Handwritten Signature]*  
11/3/2024  
Executive Engineer-III,  
Housing, GHMC.  
*[Handwritten Signature]*  
11/3/2024